

AIR SAMPLE ASBESTOS ANALYSIS

Client: Reynolds School District No. 7

Report Date: 03/01/2019

Date Received: 02/28/2019

Client Project ID: N/A

Project: Alder Elementary School

PBS Project No.: 23514.137 0003

Page No.: 1 of 1

PBS LAB ID/ CLIENT ID	DATE, LOCATION WORKER NAME, ACTIVITY, PPE, ETC.	MINUTES SAMPLED	AVE. FLOW RATE (LPM)	AIR VOLUME (L)	FIBERS/ FIELDS	FIBERS PER cc (f/cc)
A23514.137-0048	2/28/2019 - Ambient air Room 30 C: 5.5 fibers/100 fields	270	10 LPM	2700 L	2.5/100	<LOD
A23514.137-0049	2/28/2019 - Ambient air Room 29 C: 5.5 fibers/100 fields	270	10 LPM	2700 L	2/100	<LOD
A23514.137-0050	2/28/2019 - Ambient air Room 28 C: 5.5 fibers/100 fields	270	10 LPM	2700 L	4/100	<LOD

REVIEWED BY

Approved Signatory

Date

Joel McCarthy

Name

L: Liters of air

LPM: Liters per minute

A: Interlaboratory 95% Upper Confidence Limit

B: Intralaboratory 95% Upper Confidence Limit

C: Limit of detection (LOD)

<LOD: Below the limit of detection

FILTER AREA (Square millimeters): 385