

January 28, 2016

RFP– CM/GC Reynolds Middle School Gymnasium Seismic Rehab

Addendum #1

From: Robert Collins
Senior Project Manager
Day CPM Services

REQUEST FOR PROPOSALS

CM/GC Reynolds Middle School Gymnasium Seismic Rehab

Reynolds School District

The RFP for the above referenced project and the work covered are modified as follows, and except as set forth herein, otherwise remain unchanged and in full effect. This addendum is part of the RFP solicitation Documents for the above named project and modifies the original RFP Documents dated January 8, 2016. Acknowledgement of receipt of this addendum is required as part of the Proposal.

Item #1 RFP Format Adjustment:

5.4 Evaluation Criteria, (provide the spaces between the section and subsection numbers as shown for the paragraphs as shown below :)

- 5 3.2.2.7 Local business participation (10 points maximum)
- 6 3.2.3.1 Fee Proposal: Preconstruction and Construction services (20 points maximum)

Item #2 Delete entirely:

~~3.2.2.6 Subcontractor/Supplier Selection Approach~~

- ~~a. Describe in detail your firm's subcontractor and supplier procurement/selection process. Also describe how you would provide local subcontractor and supplier opportunities to submit bids to your firm. A local business is defined as a business that has an existing significant place of business located within the electoral and taxing boundaries of the Reynolds School District.~~

Item #3 Replace with:

3.2.2.5 Local Conditions/MWESBE Utilization

- a. Describe your firm's knowledge and experience with the labor market and

building conditions in the Multnomah County and City of Fairview Metro area.

- b. Demonstration of experience with local MWESB firms including a list of State of Oregon certified businesses that your firm has partnered or subcontracted within the last two (2) years, identify any MWESB firms that are part of your proposed team, and any innovative/successful measures your firm has undertaken to increase diverse business participation on projects in the Portland Metro area. Describe your approach to subcontractor and supplier procurement/selection process, and promoting participation in the project on the part of minorities, women, and emerging small business enterprises. Also describe your approach for local material suppliers, vendors, and building trades. A local business is defined as a business that has an existing significant place of business located within the electoral and taxing boundaries of the Reynolds School District.

Item #2 Change:

~~3.2.2.5 Contract Formats~~ to 3.2.2.6 Contract Formats

Item #3 Change:

5.4 Evaluations

~~5 3.2.2.7 Local business participation (10 points maximum)~~

to:

5 3.2.2.5 Local Conditions/MWESBE Utilization (10 points maximum)

Attachments:

- Signup Sheet for the Mandatory pre-proposal meeting held on January 18, 2016.
- 60% Design Documents Set by ZCS Engineering, dated 1/27./2016 to be added to information of Appendix A of the RFP dated January 8, 2016.
- Environmental Report dated January 28, 2016 regarding the roofing on the project Gymnasium by PBS Engineering + Environmental.

End of Addendum #1

Date | time 1/18/16 10:00 AM

Reynolds Middle School
1200 NE 201st Ave. Fairview, OR 97204

Company Name	Attendee Name	E-Mail	Office Phone	cell phone
KIRBY MACZELHOUT Construction Company	CHRISTOPHER PRATT	CHRISP@KIRBYMACZELHOUT.COM	503-530-8420	503-522-1340
ZCS Engineering	Shawn Wilson	Shawn@ZCSEngineering.com		503-544-8377
ZCS Eng.	Zack Stokes	Zack@ZCSEngineering.com	503-659-2205	
ROBINSON Construction Co.	RYAN WEEHUNT	RWEEHUNT@ROBCON.COM	(503) 645-8531	503-209-8564
Alexi Mennissen	Brennik Construction	AM@brennik.com	503.668.1000	503.914.9672
P&C Construction	Sabrina Henkhaus	SHENKHAUS@BUILTBYPANDC.COM	503-665-0145	503-360-5204
EMERICK THINKERS	Matt Henkhaus	matt@emerrick.com	503 777-5534	93 333 6246
Cedar Mill Const. Co.	Jim Anderson	Jim@cedarmillcc.com	503-885-9370	503-332-6618



Reynolds Middle School
1200 NE 201st Ave. Fairview, OR 97204

cell phone

[illegible]

[illegible]

REYNOLDS SCHOOL DISTRICT


REYNOLDS MIDDLE SCHOOL GYM
SEISMIC REHAB.

DATE: 1/27/16

CHECKED: JZS/CDC

DRAWN: SOW

PROJECT NO.: P-2084-15



ZCS
ENGINEERING

524 Main Street - Suite 02, Oregon City, OR 97045
(503) 696-2200 phone fax (503) 596-5133

NOT FOR CONSTRUCTION

PRELIMINARY

REGISTERED PROFESSIONAL ENGINEER
No. 12345
State of Oregon




12/3/2008
CARTER

12/3/2008
CARTER

ROOF DEMO PLAN

D1.1

12/3/2008, 12-31-17




(E) ROOF MECHANICAL UNIT ELEVATION



3
D1.1

ROOF DRAIN ELEVATION

NTS



ROOF ACCESS HATCH ELEVATION



5
D1.1

ROOF VENT ELEVATION

NTS

IF THIS BAR DOES NOT MEASURE 1-INCH IN LENGTH, THEN THE DRAWING IS NOT TO SCALE


[illegible]

REYNOLDS SCHOOL DISTRICT

REYNOLDS MIDDLE SCHOOL GYM
SEISMIC REHAB.




PROJECT NO:	P-2066-1
DRAWN:	SDN
CHECKED:	ZAS/RC
DATE:	1/27/1



PROPOSED
REFLECTIVE CEILING
PLAN

A3.1



SPECIAL NOTE:
ANY AND ALL (E) HVAC UNITS ABOVE GROUND
LEVEL SHALL BE ATTACHED TO FRAMING AND
BRACED. ALL MECHANICAL PIPING TO BE
BRACED. TYP.

[illegible]

ZCS
ENGINEERING

524 Main Street - Suite 02, Oregon City, OR 97045
(503) 659-2205 phone fax (503) 659-2433

NOT FOR CONSTRUCTION
REGISTERED PROFESSIONAL ENGINEER
JAMES W. CARTER
16, 1986
EXPIRES: 12-31-17
PROPOSED ROOF FRAMING PLAN & DETAILS

PROPOSED ROOF FRAMING PLAN & DETAILS



- ## STRUCTURAL NOTES
1. DIMENSIONS SHOWN ARE FOR REFERENCE ONLY. YOU CONFIRM W/ ARCHITECTURAL PLAN & DETAILS.
 2. COORDINATE PENETRATIONS OF SITE UTILITIES, MECHANICAL, ELECTRICAL, PLUMBING, AND HVAC WITH THE STRUCTURAL ANALYSIS IMPACT TO STRUCTURAL FRAMING. PLUMBING FIXTURES SHOWN ON FLOOR FOR REFERENCE AND POSSIBLE REMAINING CONFLICTS ONLY.
 3. G.C. TO MAKE NOTE OF ANY ROOF LIFT DAMAGE THAT MAY BE DISCOVERED DURING NEW SHEATHING & ROOFING INSTALLATION. REPORT ANY DAMAGE TO EOR.
 4. G.C. TO VERIFY QUALITY OF ALL EMBEDDED BOLTS BEFORE USING THEM AS DIAPHRAGM CONNECTION REPORT ANY DAMAGE TO EOR.



Engineering +
Environmental

Pre-Renovation Asbestos Survey

Reynolds MS North Gym
Seismic Renovation
Portland, OR

Prepared for:

Reynolds School District No. 7

General Information	1.1
Inspection Summary	1.2
Sample Inventories	2.1
Laboratory Data	Not Numbered
AHERA Certificates	Not Numbered

January 2016
Project No.: 23514.018

4412 SW Corbett Avenue, Portland, OR 97239
503.248.1939 Main
866.727.0140 Fax
888.248.1939 Toll-Free
www.pbsehv.com

GENERAL INFORMATION**BUILDING DATA**

Reynolds MS North Gym
Portland, OR

CLIENT DATA

Reynolds School District No. 7
1204 NE 201st Ave.
Fairview, OR 97024-9642

SURVEY SCOPE

PBS Engineering and Environmental Inc. (PBS) has performed a limited asbestos survey of accessible building areas in the project areas in accordance with Occupational Safety and Health Administration (OSHA) in 29 Code of Federal Regulation (CFR) 1910.1001 and compiled a report with the following information:

- The type, location, and approximate quantity of suspect asbestos-containing materials
- Bulk sampling of selected suspect building materials
- Inspection summary
- Laboratory analytical data of bulk material sampled
- Suspect PCB light ballast inspection

PBS endeavored to locate all the suspect asbestos-containing materials that may be impacted during the planned remodeling activities; however, suspect asbestos-containing materials may be present and concealed within wall, ceiling, or floor spaces. If suspect materials are uncovered during demolition activities that are not identified in this report, testing should be performed prior to impact.


PBS has conducted a physical inspection of the project areas, compiled this report consistent with the survey scope, and certifies that the information is correct and accurate within the standards of professional quality and contractual obligations.

Derek May
Project Manager
Accreditation # IR-15-0009A

 01.28.2015

Signature Date

Rich Dufresne
Prime Inspector
Accreditation # IMR-15-0264A

 01.28.2015

Signature Date



INSPECTION SUMMARY

DATES	SURVEYED BY	ACTIVITY
1/19/2016	Rich Dufresne	Inspect and Sample

PBS has investigated accessible areas in the project areas to locate suspect asbestos-containing building materials (ACBM). Suspect materials may be present in concealed areas (e.g., behind walls and under carpet). The findings are listed below.

ASBESTOS MATERIALS

The following materials either tested positive, or, based on the experience of PBS field personnel, were not tested and should be considered asbestos-containing. Materials that had mixed results are considered positive. Materials not sampled may not contain asbestos and should be tested to verify asbestos content prior to impact through demolition, renovation, etc.

(+) Tested Positive, (M) Mixed Results, (P) Presumed Positive, (T) Previously Tested Positive.

<u>Result</u>	<u>Material (type)</u>	<u>Location</u>	<u>Approx. Quantity</u>
(T)	Hard Fittings/Fiberglass	North Gym	NOT QUANTIFIED

MATERIALS THAT TESTED NEGATIVE FOR ASBESTOS

The following materials tested negative based on ASHARA sampling minimums and testing by NVLAP participating laboratories. Although no asbestos was detected, it is possible that further sampling could indicate asbestos content. It may be prudent to test prior to impact through demolition, renovation, etc.

<u>Material (type)</u>	<u>Location</u>
Built-up Roofing	North Gym; Roof
Roofing Debris	North Gym; Atop Roof
Tectum Panels	North Gym; Ceiling
Gypsum Wallboard/Joint Compound	North Gym; Interior Walls

INSPECTION SUMMARY

BACKGROUND

On January 19, 2016, PBS Engineering and Environmental Inc. (PBS) performed a pre-renovation hazardous building materials survey of the North Gymnasium at Reynolds Middle School located at 1200 NE 201st Avenue in Fairview, Oregon.

The purpose of the survey was to identify asbestos-containing building materials, lead-based paint, and other regulated building materials that may be impacted by the planned seismic improvements to the north gymnasium.

Only the portions of the school building anticipated to be impacted by the planned seismic improvements were included in this investigation. Asbestos-containing materials are known to exist in other portions of the school that are not included within the scope of this project.

This survey is compiled to satisfy requirements to perform an asbestos inspection prior to any renovation or demolition activities under Oregon Administration Regulations (OAR) 340-248-0270 and OSHA hazard communication requirements.

The following is a summary of our findings.

ASBESTOS SUMMARY

Bulk samples of suspect asbestos-containing materials (ACM) were collected by a PBS Asbestos Hazard Emergency Response Act (AHERA) accredited inspector and submitted under chain-of-custody to Lab/Cor, Inc. of Portland, Oregon, for polarized light microscopy (PLM) analysis.

Asbestos-containing hard fitting insulation is present on pipes in the gymnasium. Pipes with asbestos-containing insulation are located immediately below the effected ceiling line.

It is not anticipated that the pipe insulation will be impacted by the seismic renovations project; however, contractors must be made aware of its presence and instructed not to come into contact with it. If impact to the material is anticipated, it should be removed by a qualified asbestos abatement contractor.

No other materials tested positive for asbestos.

The ceiling and roofing structure are tectum panels overlaid with built-up roofing with a gravel ballast. The roofing tested negative at the roof hatch location. Although the samples at the roof hatch tested negative for asbestos, an additional full core sample may be warranted prior to complete roofing removal.

LEAD SUMMARY

A single representative paint chip sample was collected to determine lead concentration in paint. This sample represents the major painted interior of the North Gymnasium Building.

The paint samples were submitted under chain of custody to R.J. Lee Group in Monroeville, Pennsylvania, for lead analysis by flame atomic absorption (FLAA).

The paint sample tested below the limit of detection for lead.

INSPECTION SUMMARY

MERCURY-CONTAINING LAMPS

Florescent light fixtures are present that use mercury-containing light tubes. The light fixtures are attached by a means that will require their removal during the seismic roofing project.

Approximately 150 four-foot lamps were observed. The associated ballasts are labeled as “No PCBs.”

<u>Code</u>	<u>Material</u>	<u>Location</u>	<u>Results</u>	<u>Lab</u>
23514.018-0001	Gypsum Wallboard/Joint Compound	North gym; wallboard with joint compound		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	fine compact powder, off-white	No Asbestos Detected	
	Layer 2	compact chalky material with paper, white	No Asbestos Detected	
23514.018-0002	Gypsum Wallboard/Joint Compound	North gym; wallboard with joint compound		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	fine compact powder, off-white with paint, brown	No Asbestos Detected	
	Layer 2	compact chalky material with paper, white	No Asbestos Detected	
23514.018-0003	Tectum	North gym; ceiling, ceiling panels		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	thick fibers, tan with coating, white	No Asbestos Detected	
23514.018-0004	Built-up Roofing	North gym; roofing, lower layer on tectum panels		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	fibrous tar, black	No Asbestos Detected	
	Layer 2	thick fibers, tan with coating, white	No Asbestos Detected	
23514.018-0005	Built-up Roofing	North gym; roofing, lower layer on tectum panels		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	fibrous tar, black	No Asbestos Detected	
	Layer 2	thick fibers, tan with coating, white	No Asbestos Detected	
23514.018-0006	Built-up Roofing	North gym; roofing, roofing debris at access		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	thick fibrous tar, black	No Asbestos Detected	
23514.018-0007	Built-up Roofing	North gym; roofing, roofing debris at access		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	rocky fibrous tar, black	No Asbestos Detected	
23514.018-0008	Built-up Roofing	North gym; roofing, roofing debris at access		Lab Cor
	Layer:	Description:	Analysis:	
	Layer 1	paint, silver	No Asbestos Detected	
	Layer 2	tar, black	No Asbestos Detected	

<u>Code</u>	<u>Material</u>	<u>Analysis</u>	<u>Location</u>	<u>Lab</u>
PAINT				
LB23514.018-1001	Paint	<93 ppm	North gym; wall, concrete, beige, fair condition	R.J. Lee Group

**Lab/Cor Portland, Inc.**4321 SW Corbett Ave., Ste A
Portland, OR 97239**BULK SAMPLE ASBESTOS ANALYSIS**Phone: (503) 224-5055
<http://www.labcorpdx.net>*Asbestos and Environmental Analysis***Client:** PBS Engineering and Environmental
4412 SW Corbett Avenue
Portland, OR 97239**Report Number:** 160247R01**Report Date:** 01/22/2016**Job Number:** 160247**P.O. No:** n/a**Project Name:****Project Number:** 23514.018 Phase 0001**Project Notes:**

Client Sample ID: 23514.018-0001		Sample ID: S1			Date Analyzed: 01/22/2016	Percent Asbestos:	
Client Sample Description: Progressive Analysis Group: 1					Analyst: Stephanie Golden		
<u>Asbestos Mineral Fibers</u>	Layer						
	Percent:	Chrysotile	Amosite	Crocidolite			
Layer 01							
fine compact powder, off-white	35 %	-	-	-	NAD		
Layer 02							
compact chalky material with paper, white	65 %	-	-	-	NAD		
<u>Other Fibers</u>	Fibrous Glass	Cellulose	Mineral Wool	Synthetic	Other		Matrix
Layer 01	-	-	-	-	-		100 %
Layer 02	2 %	80 %	-	-	-	18 %	

Client Sample ID: 23514.018-0002		Sample ID: S2			Date Analyzed: 01/22/2016
Client Sample Description:		Progressive Analysis Group: 1			Analyst: Stephanie Golden
<u>Asbestos Mineral Fibers</u>		Layer			Percent Asbestos:
	Percent:	Chrysotile	Amosite	Crocidolite	
Layer 01					
fine compact powder, off-white with paint, brown	95 %	-	-	-	NAD
Layer 02					
compact chalky material with paper, white	5 %	-	-	-	NAD
<u>Other Fibers</u>	Fibrous Glass	Cellulose	Mineral Wool	Synthetic	Other
					Matrix
Layer 01	-	-	-	-	-
Layer 02	-	50 %	-	-	-

**Lab/Cor Portland, Inc.**4321 SW Corbett Ave., Ste A
Portland, OR 97239**BULK SAMPLE ASBESTOS ANALYSIS**Phone: (503) 224-5055
<http://www.labcorpdx.net>*Asbestos and Environmental Analysis***Job Number: 160247****Report Number: 160247R01****Report Date: 01/22/2016**

Client Sample ID:	23514.018-0003		Sample ID:	S3		Date Analyzed:	01/22/2016	
Client Sample Description:	Progressive Analysis Group: 2		Analyst:	Stephanie Golden				
Asbestos Mineral Fibers	Layer							Percent Asbestos:
	Percent:	Chrysotile	Amosite	Crocidolite				
Homogeneous								
thick fibers, tan with coating, white	100 %	-	-	-				NAD
Other Fibers	Fibrous Glass	Cellulose	Mineral Wool	Synthetic	Other		Matrix	
	-	98 %	-	-	-	-	2 %	

Client Sample ID:	23514.018-0004		Sample ID:	S4		Date Analyzed:	01/22/2016	
Client Sample Description:	Progressive Analysis Group: 2		Analyst:	Stephanie Golden				
Asbestos Mineral Fibers	Layer							Percent Asbestos:
	Percent:	Chrysotile	Amosite	Crocidolite				
Layer 01								
fibrous tar, black	90 %	-	-	-				NAD
Layer 02								
thick fibers, tan with coating, white	10 %	-	-	-				NAD
Other Fibers	Fibrous Glass	Cellulose	Mineral Wool	Synthetic	Other		Matrix	
Layer 01	-	65 %	-	-	-	-	35 %	
Layer 02	-	98 %	-	-	-	-	2 %	

Client Sample ID:	23514.018-0005		Sample ID:	S5		Date Analyzed:	01/22/2016	
Client Sample Description:	Progressive Analysis Group: 2		Analyst:	Stephanie Golden				
Asbestos Mineral Fibers	Layer							Percent Asbestos:
	Percent:	Chrysotile	Amosite	Crocidolite				
Layer 01								
fibrous tar, black	95 %	-	-	-				NAD
Layer 02								
thick fibers, tan with coating, white	5 %	-	-	-				NAD
Other Fibers	Fibrous Glass	Cellulose	Mineral Wool	Synthetic	Other		Matrix	
Layer 01	-	65 %	-	-	-	-	35 %	
Layer 02	-	98 %	-	-	-	-	2 %	

**Lab/Cor Portland, Inc.**4321 SW Corbett Ave., Ste A
Portland, OR 97239**BULK SAMPLE ASBESTOS ANALYSIS**Phone: (503) 224-5055
<http://www.labcorpdx.net>*Asbestos and Environmental Analysis***Job Number:** 160247**Report Number:** 160247R01**Report Date:** 01/22/2016

Client Sample ID:	23514.018-0006	Sample ID:	S6	Date Analyzed:	01/22/2016	
Client Sample Description:	Progressive Analysis Group: 3			Analyst:	Stephanie Golden	
Asbestos Mineral Fibers	Layer					Percent Asbestos:
	Percent:	Chrysotile	Amosite	Crocidolite		
Homogeneous						
thick fibrous tar, black	100 %	-	-	-		NAD
Other Fibers	Fibrous	Mineral				
	Glass	Cellulose	Wool	Synthetic	Other	Matrix
	25 %	-	-	-	-	75 %

Client Sample ID:	23514.018-0007	Sample ID:	S7	Date Analyzed:	01/22/2016	
Client Sample Description:	Progressive Analysis Group: 3			Analyst:	Stephanie Golden	
Asbestos Mineral Fibers	Layer					Percent Asbestos:
	Percent:	Chrysotile	Amosite	Crocidolite		
Homogeneous						
rocky fibrous tar, black	100 %	-	-	-		NAD
Other Fibers	Fibrous	Mineral				
	Glass	Cellulose	Wool	Synthetic	Other	Matrix
	-	-	-	-	-	100 %

Client Sample ID:	23514.018-0008	Sample ID:	S8	Date Analyzed:	01/22/2016	
Client Sample Description:	Progressive Analysis Group: 3			Analyst:	Stephanie Golden	
Asbestos Mineral Fibers	Layer					Percent Asbestos:
	Percent:	Chrysotile	Amosite	Crocidolite		
Layer 01						
paint, silver	65 %	-	-	-		NAD
Layer 02						
tar, black	35 %	-	-	-		NAD
Other Fibers	Fibrous	Mineral				
	Glass	Cellulose	Wool	Synthetic	Other	Matrix
Layer 01	-	-	-	-	-	100 %
Layer 02	-	-	-	-	-	100 %



Lab/Cor Portland, Inc.

4321 SW Corbett Ave., Ste A
Portland, OR 97239

BULK SAMPLE ASBESTOS ANALYSIS

Asbestos and Environmental Analysis

Phone: (503) 224-5055
<http://www.labcorpdx.net>

Job Number: 160247

Report Number: 160247R01

Report Date: 01/22/2016

This laboratory participates in the National Voluntary Laboratory Accreditation Program (NVLAP).
Testing method is per 40 CFR 763 Subpart E, Appendix A, PLM.

Layered samples are considered non-homogeneous. "Misc" is miscellaneous. "NAD" is No Asbestos Detected.

Asbestos consists of the following minerals: chrysotile, amosite, crocidolite, tremolite, actinolite, anthophyllite.

Small diameter fibers such as those found in vinyl floor tiles, may not be detected by PLM.

Asbestos detection interferences may result from material binders.

Qualitative and quantitative TEM analysis may be recommended for difficult samples.

Quantitative analysis by PLM point count or TEM is recommended for samples testing at < or = to 1% asbestos.

The following estimate of error for this method by visual estimation of asbestos percent are as follows:

1% asbestos: 0-3% error, 5% asbestos: 1-9% error, 10% asbestos: 5-15% error, 20% asbestos: 10-30% error.

This report pertains only to the samples listed on the report. Report considered valid only when signed by analyst.

Reviewed by:


X

Stephanie Golden

Technical Manager



Engineering +
Environmental

160247

TRANSMITTAL AND CHAIN OF CUSTODY FOR ASBESTOS BULK SAMPLES

Project No.: 23514.018 Phase 0001

Individuals signing this form warrant that the information provided is correct and complete. The Sender should keep a copy and send the original. The Receiver should complete the form, keep a copy and return the original to the Sender. Receiver shall report damage of package immediately to Sender.

SENDER

Date Sent: January 20, 2016

PBS Engineering and Environmental Inc.
4412 SW Corbett Avenue
Portland, OR 97239
503.248.1939, Fax: 866.727.0140

JAMES BLANCO
Name 12:55

[Signature] 1/20/16
Authorized Signature Date

RECEIVER

Date Received: 1/20/16 1:00pm

Company: Lab Cor
Address: 4321 SW Corbett Ave Ste A
Portland, OR 97239
503-224-5055

STEPHANIE GOWEN
Name

[Signature] 1/20/16
Authorized Signature Date

Sender's ID No.	Brief Description	Receiver's ID No.
23514.018-0001 }	Progressive Analysis Group: 1	
23514.018-0002 }	" 1	
23514.018-0003 }	Progressive Analysis Group: 2	
23514.018-0004 }	" 2	
23514.018-0005 }	" 2	
23514.018-0006 }	Progressive Analysis Group: 3	
23514.018-0007 }	" 3	
23514.018-0008 }	" 3	

Please analyze the enclosed 8 sample(s) for asbestos content using PLM with dispersion staining. PBS requests prior notification if samples will be disposed.

Request verbal results by: _____ AM/PM _____ Date.

Please fax and mail the results to the above address.

TURNAROUND DESIRED: 48 Hour

SPECIAL INSTRUCTIONS:

Please note the progressive analysis groups defined above.

RD

LABORATORY REPORT

 PBS Engineering & Environmental
 4412 Southwest Corbett Ave.
 Portland, OR 97239

 Attn: James Blanco
 Phone: 503-248-1939
 Fax: 503-248-0223
 Email: james.blanco@pbsenv.com

 RJ Lee Group Job No.: PA210120160012
 Samples Received: January 21, 2016
 Report Date: January 22, 2016
 Client Project: 23514.018 Phase 0001
 Purchase Order No.: N/A
 Matrix: Solid
 Prep/Analysis: EPA 3050B / EPA 7000B-Paint

Client Sample ID	RJ Lee Group ID	Sampling Date	Analyte	Sample Concentration			Minimum Reporting Limit			Analysis Date	Q
				Weight Percent (%)	Parts per Million (PPM) - mg/kg	Parts per Million (PPM) - mg/kg	Weight Percent (%)	Parts per Million (PPM) - mg/kg	Parts per Million (PPM) - mg/kg		
LB23514.018-1001	PA210120160012-001	NP	Lead	< 0.0093	< 93		0.0093	93		01/22/2016	AN

Comments:

Report Qualifiers (Q):

P : PA-DEP Accredited (PA DEP Lab ID 02-00396, NELAP)
 N : NY ELAP Accredited (NY ELAP Lab Code 10884)
 C : CA ELAP Accredited (CA ELAP Certificate 1970)
 A : AIHA-LAP, LLC Accredited (Lab ID 100364)
 — : Test (analyzer-matrix-preparation-analysis) is performed under RJLG's General Quality System requirements and is not part to any of the above scopes of accreditations

E = Value above highest calibration standard

J = Value below lowest calibration standard but above MDL (Method Detection Limit)

L = LCS (Laboratory Control Standard)/SRM (Standard Reference Material) recovery outside accepted recovery limits

H = Holding times for preparation or analysis exceeded

— : Test (analyzer-matrix-preparation-analysis) is performed under RJLG's General Quality System requirements and is not part to any of the above scopes of accreditations

These results are submitted pursuant to RJ Lee Group's current terms and conditions of sale, including the company's standard warranty and limitation of liability provisions. No responsibility or liability is assumed for the manner in which the results are used or interpreted. Unless notified in writing to return the samples covered by this report, RJ Lee Group will store the samples for a period of thirty (30) days before discarding. A shipping and handling fee will be assessed for the return of any samples.

This laboratory operates in accord with ISO 17025:2005 guidelines, and holds a limited scope of accreditations under different accrediting agencies; refer to <http://www.rjlg.com/about-us/accreditations/> for more information and current status. Unless it is specifically stated otherwise (under the Q column using the appropriate accrediting agency qualifier(s)) the work contained in this report is performed under RJLG's General Quality System requirements and is not part of any scope of accreditations. This report may not be used to claim product endorsement by any laboratory accrediting agency. The results contained in this report relate only to the items tested or to the sample(s) as received by the laboratory. Any reproduction of this document must be in full for the report to be valid.

Unless otherwise noted (either in the comments section of the report and/or with the appropriate qualifiers under the report qualifiers (Q) column) the following apply: (a) Samples were received in good condition, (b) All QC samples are within acceptable established limits, (c) All samples designated as NELAP meet the requirements of the NELAC standard; if not applicable qualifiers will be used to designate the non-compliance and (d) Results have not been blank corrected. Quality Control data is available upon request.

B = Analyte detected in the associated Method Blank
 S = Spike Recovery outside accepted limits
 R = RPD (relative percent difference) outside accepted limits
 D = RL (reporting limit verification) outside accepted limits
 NP = Not Provided



Philip Grindle
Laboratory Supervisor



Engineering +
Environmental

PA210120160012

TRANSMITTAL AND CHAIN OF CUSTODY FOR LEAD BULK SAMPLES

Project No.: 23514.018 Phase 0001

Individuals signing this form warrant that the information provided is correct and complete. The Sender should keep a copy and send the original. The Receiver should complete the form, keep a copy and return the original to the Sender. Receiver shall report damage of package immediately to Sender.

SENDER

Date Sent: January 20, 2016

PBS Engineering and Environmental Inc.
4412 SW Corbett Avenue
Portland, OR 97239
503.248.1939, Fax: 866.727.0140

JAMES BLANCO
Name
[Signature] 12:50
Authorized Signature Date

RECEIVER

Date Received: 01/21/16

Company: R.J. Lee Group
Address: 350 Hochberg Road
Monroeville, PA 15146
724-325-1776

J OAKLEY 100
Name
[Signature] 01/21/16
Authorized Signature Date

Sender's ID No.

LB23514.018-1001

Brief Description

Receiver's ID No.

ANALYSIS REQUESTED:

- LEAD: ☒ Paint
☐ Wipe
☐ Soil/Misc.
☐ Air
☐ TCLP

Please analyze the enclosed 1 sample(s) for LEAD content using Atomic Absorption Method. PBS requests prior notification if samples will be disposed.

Please fax and mail the results to the above address.

TURNAROUND DESIRED:

48 Hour

SPECIAL INSTRUCTIONS:

RD

THIS IS TO CERTIFY THAT

RICH A. DUFRESNE

HAS SUCCESSFULLY COMPLETED THE TRAINING COURSE

for

**ASBESTOS INSPECTOR / MANAGEMENT
PLANNER REFRESHER**

In accordance with TSCA Title II, Part 763, Subpart E, Appendix C of 40 CFR

Course Date: 04/02/2015
Course Location: Portland, OR
Certificate: IMR-15-0264A



**Engineering +
Environmental**

Expiration Date: 04/02/2016

AHERA is the Asbestos Hazard
Emergency Response Act enacting Title II
of Toxic Substance Control Act (TSCA)

For verification of the authenticity of this
certificate contact:
PBS Environmental
4412 SW Corbett Avenue
Portland, OR 97239
(503) 248-1939

David Stover

David Stover, Director of Training

THIS IS TO CERTIFY THAT

DEREK MAY

HAS SUCCESSFULLY COMPLETED THE TRAINING COURSE
for
ASBESTOS INSPECTOR REFRESHER

In accordance with TSCA Title II, Part 763, Subpart E, Appendix C of 40 CFR

Course Date: 04/10/2015

Course Location: Portland, OR

Certificate: IR-15-0009A



**Engineering +
Environmental**

Expiration Date 04/10/2016

Refresher Training Completed Online

For verification of the authenticity of this
certificate contact:
PBS Environmental
4412 SW Corbett Avenue
Portland, OR 97239
(503) 248-1939

A handwritten signature in black ink, which appears to read "David Stover".

David Stover, Director of Training